Genie SLC 18 - Material Lift



Specifications

Specifications		
Model	SLC-18	
Measurements	US	Metric
Working height:		
standard forks - down	16 ft 9 in	5.10 m
standard forks - up	18 ft 6 in	5.64 m
A Height - stowed	7 ft 2 in	2.18 m
Length - stowed	2 ft 10 in	.86 m
Length - operating	6 ft 1 in	1.85 m
🕰 Width - stowed	2 ft 7.5 in	.80 m
- with stabilizers lowered	5 ft 6 in	1.68 m
Width - straddle base		
minimum		
maximum		
maximum inside		
Ground clearance - center	2	.05 m
Load height minimum	6 in	.15 m
Productivity		
Load capapcity:		205 4-2
14 in (36 cm) load centre 24 in (61cm) load centre	650 lbs 425 lbs	295 kg 193 kg
42 in (107 cm) load centre	160 lbs	73 kg
	100100	, , , , ,
Power		
Average cranks - per length unit		
standard winch -	8.5 ft	27.8 m
Weight		
Standard	307 lbs	139 kg
Straddle base		
Load Handling Attachments		
Measurements	US	Metric
Standard	28/23/2.5 in	71/58/6 cm
Weight	26.5 lbs	12 kg
	20.5 105	12 16

Standard Features

- Heavy-duty design
- Patented telescoping mast system
- Rolls easily through single door in upright position
- Quick set up requires no tools
- Interchangeable load handling attachments
- Maneuverable 4 in (10 cm) front casters and 5 in (13 cm) rear casters, with 4-way swivel locks and side brakes
- Compact design, legs fold up for easy storage
- Easy to load and unload on or off a vehicle for transport
- Hold-down bar secures mast assembly during transport
- Winch locks load in place
- Captive stabiliser set (standard on SLC 18 and 24)



